

ADDENDUM NO. 1

DATE: April 29, 2016
FROM: Village of Villa Park Public Works Department
TO: All Potential Bidders
PROJECT: **2016 Street Improvements**

The Bidding Documents for the subject project are hereby amended as follows. Please indicate your acknowledgment of this Addendum by filling out the attached Acknowledgment Form and returning it with your Bid.

CHANGE THE FOLLOWING ITEM(S) IN THE SPECIFICATIONS:

IN "NOTICE TO BIDDERS":

REPLACE:

Replace Page 2 of 9 of the BLR 12200 form with the attachment included in this addendum. The revisions made to this page are as follows:

Sealed proposals for the improvement described below will be received at the office of Villa Park Public Works Department, 11 West Home Avenue, Villa Park, IL 60181 until 10:00 AM on **May 5, 2016**.

Sealed proposals will be opened and read publicly at the office of Villa Park Public Works Department, 11 West Home Avenue, Villa Park, IL 60181 at 10:00 AM on **May 5, 2016**.

IN THE SPECIAL PROVISION “COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT”:

REPLACE THE ENTIRE SPECIAL PROVISION WITH:

COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT

Description. This work shall consist of the removal and replacement of combination concrete curb and gutter of the various types, as directed by the Engineer. This work shall be done in accordance with Section 440 and Section 606 of the Standard Specifications and Standard No. 606001, with the following modifications:

All work shall follow and be according to District One Detail BD-24 “Curb or Curb and Gutter Removal and Replacement” except that the Contractor will be required to saw cut 8” off the edge of pavement. The removal of the 8” wedge will be included in the cost of this item. The void between the existing base and the new gutter will be filled in with a minimum thickness of 8” of concrete. This concrete wedge will be placed after the curb and gutter has been poured and the framing has been removed. In addition, 1” expansion joints shall be constructed at maximum intervals of 100 feet. Concrete curing methods shall be limited to the methods specified in Article 1020.13 (a) (1), (2), and (3) of the Standard Specifications. Contraction joints shall not exceed 15’ intervals and shall initially be tooled and then saw cut within 24 hours of pouring the curb and gutter. This additional work will not be paid for separately but shall be included in the cost of this item.

Depressed curb for driveway openings, sidewalk ramps accessible to the disabled, and any other designated areas shall be constructed at the locations shown on the plans or as designated by the Engineer. There may be certain areas of curb and gutter that have depressed curbs in locations that do not warrant such depressions. The Engineer may decide in the field to replace these locations to a barrier curb and gutter. Any variations in curb height, gutter width, or other modifications to meet or alter existing conditions will not be paid for separately but shall be included in the cost of this item.

Basis of Payment. This work will be paid for at the contract unit price per foot for COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT; which price shall include all materials, labor and equipment necessary to complete the work as described herein.

INSERT THE NEW SPECIAL PROVISION “COMBINATION CURB AND GUTTER REMOVAL”:

INSERT:

COMBINATION CURB AND GUTTER REMOVAL

Description. This work shall consist of removing combination curb and gutter as shown on the plans or as directed by the Engineer according to Section 440 of the Standard Specifications, with the following modifications:

The Contractor shall saw cut 8” off the edge of pavement. This work along with the removal of the 8” wedge will not be paid for separately but shall be included in the cost of this item.

Basis of Payment. This work will be paid for at the contract unit price per foot for COMBINATION CURB AND GUTTER REMOVAL; which price shall include all materials, labor and equipment necessary to complete the work as described herein.

INSERT THE NEW SPECIAL PROVISION “COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12”:

INSERT:

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12

Description. This work shall consist of constructing combination concrete curb and gutter, type B-6.12 as shown in the plans or as directed by the Engineer according to Section 606 of the Standard Specifications, with the following modifications:

The void between the existing base and the new gutter will be filled in with a minimum thickness of 8” of concrete. This concrete wedge will be placed after the curb and gutter has been poured and the framing has been removed. The placement of the concrete wedge will not be paid for separately but shall be included in the cost of this item.

Basis of Payment. This work will be paid for at the contract unit price per foot for COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12; which price shall include all materials, labor and equipment necessary to complete the work as described herein.

ADDENDUM NO. 1 ACKNOWLEDGMENT FORM

I/We hereby acknowledge receipt of the following documents pertaining to **ADDENDUM No. 1** to the Bidding Documents for the Village of Villa Park's **2016 STREET IMPROVEMENTS** project.

Addendum No. 1

3 pages

Name: _____

Title: _____

Company: _____

Signature: _____

Date: _____